ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notification dated 22nd April 1936.

Attention of the public is invited to the Notification, calling for tenders for the work of laying pipe lines for rising main and distribution lines for giving water supply to White-Field Town, published on pages 602-603, Part VI of the *Mysore Gazette*, dated 30th April 1936.

The last date for receipt of tenders is 18th May 1936.

B. R. GARUDACHAR,
Sanitary Engineer.

BANGALORE BUILDINGS DIVISION.

Notification, dated 8th May 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 30th May 1936, till 2 P.M. for constructing the Arya Balika Patasala near the temple of Kasi Visvesvara, Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one thousand and fifty only (Rs. 1,050) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the Arya Balika Patasala near the temple of Kasi Visveswara, Bangalore City", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Transfer of works to third parties by selected contractors will not be countenanced by the department and in the case of any such attempt the earnest money is liable to be forfeited at the discretion of the Superintending Engineer. Quotation for wood work must be for the use of Mysore teak only.

Abstract estimate of quantities for constructing Arya Balika Patasala, Bangalore City.

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation for foundation and refilling basement including watering and tamping	C.yds.	0 3 6	362	
2	Concrete stone jelly in lime mortar 1 : 2 : 4, including watering and tamping ..	C.ft.	0 3 6	2,079	
3	Size stone in lime mortar 1 : 2 with bond stones 6′ apart in foundation and basement with 1′ quoin dressing at exposed corners	,,	0 5 0	6,914	
4	Burnt stone slabs 6″ thick, two line dressed in exposed faces, one line dressed in other portions and laid in lime mortar ..	S.ft.	0 6 0	1,531	
5	Size stone in lime mortar, 1 : 2 for superstructure, including bond stones, 6′ apart and 1″ quoin dressing at all corners and with neat clear joints	C.ft.	0 5 6	5,043	
6	Burnt brick in lime mortar	,,	0 4 6	1,958	
7	Teakwood doors 3″×5″ frame $1\frac{1}{2}$″ thick shutters, $\frac{2}{3}$ glazed $\frac{1}{3}$ panelled including brass parliamentary hinges, bolts, hooks, etc., and rectangular glazed fan light, complete	S.ft.	1 10 0	252	
8	Teakwood windows 3″×5″ frame $\frac{3}{4}$″ thick shutters fully glazed in four leaves, including $\frac{3}{4}$″ iron bars at 4″ centre, brass parliamentary hinges, bolts, hooks, etc., and rectangular glazed fan light complete	,,	1 12 0	456	
9	Size stone in lime mortar, 1 : 2 pillars in Verandah with through bond slabs for every 4′ height with neat clear joints and 1″ quoin dressing including white cement pointing, etc., complete ..	C.ft.	0 8 0	788	
10	Cut stone bases and capitals as per design, including hoisting and fixing in lime mortar and cement pointed	Set	8 0 0	14	
11	Tata's tested R.S. Beams and joints, including hoisting and fixing with necessary distance pipes, bolts, etc., and either two coats of approved paint or boxing with brick bats in cement mortar	Cwt.	10 0 0	96	
12	Burnt stone slabs 8″ thick, three line dressed at top and one line dressed in other faces and set in lime mortar	S.ft.	0 8 0	68	
13	Roofing with reinforced cement concrete, 1: 2 : 4, interspersed with good burnt bricks on edge designed to carry a safe load of two cwts. per s.ft. for a clear span of 8′ including smooth lime mortar plastering for ceiling with coning	Sqr.	60 0 0	31·08	

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
14	Flooring with cement concrete 1 : 2 : 4, $1\frac{1}{2}''$ thick on 3″ lime concrete laid over 9″ of sand and boulder filling top finished with $\frac{1}{2}''$ cement plaster mixed with red oxide with cut lines and rendering off corners	Sqr.	25 0 0	26·55	
15	Plastering with lime mortar, three coats on stone work	,,	3 8 0	32·06	
16	Plastering with lime mortar, two coats over brick work	,,	3 0 0	25·20	
17	Colour washing, two coats as per item No. 15 and 16	,,	0 5 0	57·26	
18	Constructing teakwood staircase with ceiling as per design, including varnishing, two coats	S.ft.	3 12 0	124	
19	Providing and fixing C.I. railing as per design with teakwood hand tail, 3″×4″ and newal pests, etc., including varnishing two coats	R.ft.	2 4 0	43	
20	White cement pointing after raking joints $\frac{1}{2}''$ deep	Sqr.	4 0 0	41·56	
21	Silicate painting, two coats	,,	3 8 0	11·25	
	FIRST FLOOR.				
1	Size stone in lime mortar, 1 : 2 for superstructure with bond stones 6′ apart with neat clear joints and 1″ quoin dressing at all corners	C.ft.	0 6 0	4,760	
2	Burnt brick in lime mortar	,,	0 5 0	1,468	
3	Burnt stone slabs, 6″ thick, two line dressed in exposed faces and below girders and one line dressed in other portions and laid in lime mortar	S.ft.	0 8 0	645	
4	Teakwood doors 3″×5″ frame, $1\frac{1}{2}''$ thick shutters $\frac{1}{3}$ panelled $\frac{2}{3}$ glazed, including brass parliamentary hinges, bolts, hooks, etc., with rectangular glazed fan light ..	,,	1 11 0	216	
5	Teakwood windows, 3″×5″, frame $1\frac{1}{4}''$ thick, shutters fully glazed in four leaves including $\frac{3}{4}''$ iron bars at 4″ Centres, brass parliamentary hinges, bolts, hooks, etc., with rectangular glazed fan light ..	,,	1 13 0	480	
6	Pillars of sized stone, in lime mortar 1 : 2 with through bond slabs for every 4′ height, with neat clear joints and 1″ quoin dressing, including white cement pointing, etc., complete	C.ft.	0 8 6	693	
7	Cut stone bases and capitals as per design, including hoisting and fixing in lime mortar and cement pointed	Sets	8 0 0	14	
8	Tata's tested R.S. Beams and joists including hoisting and fixing with necessary distance pipes, bolts, etc., and either two coats of approved paint or boxing with brick bats in cement mortar	Cwt.	10 8 0	67·18	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
9	Roofing with reinforced cement concrete, 1 : 2 : 4 interspersed with good burnt bricks designed to carry a safe load of 1½ cwts. per S.ft. for a clear span of 8′ including smooth lime plaster for ceiling with coning and 3″ surki concrete, two courses of flat tiles laid in lime mortar top finished with ½″ smooth lime plaster with necessary slope for drainage	Sqr.	70 0 0	29·32	
10	Roofing similar to item No. 9 but for a clear span of 10½′	,,	75 0 0	2·09	
11	Flooring with 1½″ thick cement concrete, 1 : 2 : 4 on 3″ surki concrete top finished with ½″ cement plaster mixed with red oxide with cut lines and rounding off corners	,,	25 0 0	28·47	
12	Providing and fixing C.I. railing in verandah as per design including painting two coats and T.W. polished hand rail, 3″×4″ ..	R.ft.	2 4 0	84	
13	Plastering with lime mortar, three coats over stone work	Sqr.	3 12 0	32·34	
14	Plastering with lime mortar, two coats over brick work	,,	3 4 0	25·20	
15	Colour washing, two coats as per item No. (13 14)	,,	0 5 0	57·54	
16	White cement pointing after raking joints, ½″ deep	,,	4 8 0	36·39	
17	Silicate painting, two coats	,,	3 12 0	10·98	
18	Cut stone cornice (modern) as per design, 12″ deep with flutings as per drawing laid in lime mortar and pointed with white cement	R.ft.	1 8 0	110	
19	Sized stone in lime mortar parapet wall modern design as per drawing 2½′ high, 1′ thick with blocking course and coping slab, one line dressed, including pointing with white cement and Q.C. C. panel in the central portion	,,	2 4 0	301	
20	Sized stone in lime mortar parapet wall similar to above but 1½′ high	,,	1 12 0	108	
21	Constructing compound wall with burnt brick in mud 4½′ high, 9″ thick, including base and coping with necessary foundation and lime mortar plastering and white washing complete	,,	2 4 0	380	
22	Providing and fixing M.S. gates as per design including two coats of painting ..	S.ft.	1 6 0	120	

N. KRISHNA IYENGAR,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 25th April 1936.

The attention of the public is invited to the notification, on pages 604-605 of the issue of *Mysore Gazette*, Part VI, dated 30th April 1936, calling for tenders for the work of Restoration of breached Byranahalli Minor Tank, Register No. 35, Narasapur Hobli, Malur Taluk.

The last date fixed for the receipt of tenders in this Office is 2 P.M., on 25th May 1936.